

# K-Childcare LPL/HPL/Compact Partition System

## 5214 KERMAC TOILET PARTITION SYSTEMS

### 1. GENERAL

This section relates to the supply and installation of **KerMac** partitioning systems using proprietary, prefabricated toilet partitions and screens.

It includes;

- K-Childcare Toilet Partitions System

### 1.1 RELATED WORK

Refer to ~ for ~

#### Documents

### 1.2 DOCUMENTS

Refer to the general section 1233 REFERENCED DOCUMENTS. The following documents are specifically referred to in this section:

[NZBC C/AS1-AS7](#) Protection from fire

JIS Z 2801 Antibacterial products - Test for antibacterial activity and efficacy

### 1.3 MANUFACTURER/SUPPLIER DOCUMENTS

Manufacturer's and supplier's documents relating to this part of the work:  
K-Childcare Brochure

Fire Test Report FH 5026, Group Classification 3 for Low Pressure laminate (Laminex New Zealand)

Fire Test Report 7-598418-CV, Group Classification 3 for High Pressure Laminate (Laminex New Zealand)

Fire Test Report 7-598692-CV, Group Classification 3 for Compact laminate (Laminex New Zealand)

Manufacturer/supplier contact details

Company: KerMac Industries

Web: [www.kermac.co.nz](http://www.kermac.co.nz)

Email: [kerry@kermac.co.nz](mailto:kerry@kermac.co.nz)

Telephone: 09 273 1524

#### Warranties

### 1.4 WARRANTY - MANUFACTURER/SUPPLIER

Provide a material manufacturer/supplier warranty:

5 years For panel integrity

2 years Hardware

- Provide this warranty on the manufacturer/supplier standard form.
- Commence the warranty from the date of practical completion of the contract works.

Refer to the general section 1237 WARRANTIES for additional requirements.

### 1.5 WARRANTY - INSTALLER/APPLICATOR

Provide an installer/applicator warranty:

2 years For installation

- Provide this warranty on the installer/applicator standard form.
- Commence the warranty from the date of practical completion of the contract works.

Refer to the general section 1237 WARRANTIES for additional requirements.

## **Requirements**

- 1.6 **QUALIFICATIONS**  
Installers to be experienced, competent trades people familiar with the materials and techniques specified.
- 1.7 **NO SUBSTITUTIONS**  
Substitutions are not permitted to any of the specified **KerMac** systems, components and associated products listed in this section.
- 1.8 **SAMPLES**  
Submit on request samples of panels and componentry for approval of colour and finishes.

## **Performance**

- 1.9 **SURFACE FIRE PROPERTIES**  
Group Number to [NZBC C/AS2-AS7](#), table 4.1. Refer to SELECTIONS.

## **2. PRODUCTS**

### **Materials – K-Childcare toilet partition system**

- 2.1 **CHANNELS, RAILS AND BRACKETS**  
Extruded aluminium alloy 6060 with exposed face anodic coated.
- 2.2 **PANELS - MDF**  
18mm MDF with factory applied low pressure laminate in low abuse, dry areas.  
16mm MDF core faced with high pressure laminate. Silver anodised aluminium edge trim to perimeter of all panels.
- 2.3 **PANELS - COMPACT LAMINATE**  
13mm compact laminate panels with black core. Edges polished finish only.  
13mm Swiss CDF panels with black core. Edges polished finish only.  
antimicrobial to JIS Z 2801 to prevent the growth of bacteria on the surface up to 99% within 24 hours.
- 2.4 **DOORS**  
To match the rigid panels complete with PVC edging or Machined to 4 sides.

## **Components**

- 2.5 **HINGES**  
To match the aluminium section in size, 3 hinges per door.  
Type: Spring, stainless steel finish
- 2.6 **PEDESTALS**  
Metal standard with flanged top and bottom to screw fix to panel and floor.  
Type: Cast metal

## **3. EXECUTION**

### **Conditions**

- 3.1 **DELIVERY, STORAGE AND HANDLING**  
Take delivery, handle and store tracks, studs, panels and accessories on site on a level floor and cover.  
Protect finished surfaces, edges and corners from damage.  
Move/handle goods in accordance with manufacturer's requirements.  
Reject and replace goods that are damaged or will not provide the required finish.

- 3.2 **PRE-INSTALLATION REQUIREMENTS**  
Check work previously carried out and confirm it is of the required standard for this part of the work. Ensure substrate plumb, level and in true alignment.

**Application**

- 3.3 **INSTALL SCREENS**  
Carry out the fixing, erection and fitting to finish rigid, plumb, true to line and face and square, to KerMac Industries requirements.

- 3.4 **INSTALL COMPONENTS**  
Hang doors and fit hardware to the KerMac Industries requirements.

**Completion**

- 3.5 **ROUTINE CLEANING**  
Carry out routine trade cleaning of this part of the work including periodic removal of all debris, unused and temporary materials and elements from the site.

- 3.6 **DEFECTIVE OR DAMAGED WORK**  
Repair damaged or marked elements. Replace damaged or marked elements where repair is not possible or will not be acceptable. Leave work with parts fully and freely working to the standard required for following procedures.

**4. SELECTIONS**

For further details on selections go to [www.kermac.co.nz](http://www.kermac.co.nz)  
Substitutions are not permitted to the following, unless stated otherwise.

**Performance**

- 4.1 **SURFACE FIRE PROPERTIES**

Group Number	Panel/Finish	Location
~	Low Pressure Laminate High Pressure Laminate Compact Laminate	~

Fire Test Report FH 5026, Group Classification 3 for KerMac LPL (Laminex New Zealand)

Fire Test Report 7-598418-CV, Group Classification 3 for KerMac HPL (Laminex New Zealand)

Fire Test Report 7-598692-CV, Group Classification 3 for Compact laminate (Laminex New Zealand)

**Materials - partition system**

**K-CHILDCARE LPL/HPL/COMPACT/SWISS CDF TOILET PARTITION SYSTEM**

- 4.2

Brand:	<b>KerMac Industries</b>
System type:	<b>K-Childcare LPL/HPL/Compact Toilet Partition System</b>
Panel description:	18mm Low Pressure Laminate/High Pressure Laminate or 13mm Compact laminate/Swiss CDF
Panel colour:	~
Component colour	Channels/Rails/Brackets, Natural Silver anodised
Pedestal Height	100mm
Hardware	Satin chrome finish